

**Percent Distribution of New Privately Owned Residential Buildings Completed in Permit-Issuing Places in 2002  
by Number of Months from Start**

	Buildings with 1 unit				Buildings with 2 units or more				
	Total <sup>1</sup>	Purpose of construction			Total	Number of units in building			
		Built for sale	Contractor-built	Owner-built		2 to 4	5 to 9	10 to 19	20 or more
<b>Percent Distribution</b> (Percents may not add to 100 due to rounding)									
<b>United States</b>									
3 months or less	21	24	18	13	5	10	2	1	(Z)
4 to 6 months	50	54	45	32	20	24	25	17	9
7 to 9 months	17	16	22	22	32	33	32	32	27
10 to 12 months	5	4	8	12	20	12	19	27	29
13 months or more	6	3	7	22	23	20	21	23	33
<b>Northeast</b>									
3 months or less	15	15	20	11	4	4	9	-	-
4 to 6 months	42	45	43	30	15	16	31	14	-
7 to 9 months	23	22	21	24	31	31	36	49	14
10 to 12 months	9	8	8	13	17	16	5	7	48
13 months or more	12	9	9	22	32	33	20	29	38
<b>Midwest</b>									
3 months or less	16	16	19	13	10	17	4	1	1
4 to 6 months	50	55	47	28	21	25	19	14	15
7 to 9 months	22	20	24	23	38	38	41	39	30
10 to 12 months	7	6	6	12	17	8	21	36	26
13 months or more	6	3	4	22	13	12	15	11	29
<b>South</b>									
3 months or less	27	31	19	15	4	14	(Z)	2	(Z)
4 to 6 months	49	52	47	34	25	38	29	22	11
7 to 9 months	14	12	19	22	29	22	32	28	33
10 to 12 months	5	3	8	10	22	13	19	24	31
13 months or more	5	3	7	18	20	13	19	24	24
<b>West</b>									
3 months or less	17	19	12	11	3	6	2	(Z)	(Z)
4 to 6 months	54	58	40	31	18	24	22	13	5
7 to 9 months	18	17	24	19	29	37	27	29	16
10 to 12 months	5	4	10	12	20	14	21	28	22
13 months or more	6	3	13	27	30	19	28	31	57

**Percent Distribution of New Privately Owned Residential Buildings Completed in Permit-Issuing Places in 2002  
by Number of Months from Start**

	Buildings with 1 unit				Buildings with 2 units or more				
	Total <sup>1</sup>	Purpose of construction			Total	Number of units in building			
		Built for sale	Contractor-built	Owner-built		2 to 4	5 to 9	10 to 19	20 or more
<b>Relative Standard Error</b>									
<b>United States</b>									
3 months or less	5	6	8	17	30	31	30	29	56
4 to 6 months	2	2	4	7	10	16	10	15	15
7 to 9 months	3	4	7	6	9	19	7	9	7
10 to 12 months	6	7	8	10	7	18	7	10	8
13 months or more	7	7	10	11	7	15	10	13	8
<b>Northeast</b>									
3 months or less	9	13	10	24	48	53	26	(A)	(A)
4 to 6 months	5	6	12	9	22	27	42	33	(A)
7 to 9 months	6	9	21	9	15	17	28	28	44
10 to 12 months	8	13	22	15	18	16	36	39	33
13 months or more	12	16	27	12	14	14	35	72	57
<b>Midwest</b>									
3 months or less	12	15	21	22	53	53	57	66	89
4 to 6 months	4	4	4	13	26	36	28	38	54
7 to 9 months	6	8	15	13	27	50	16	17	22
10 to 12 months	14	12	20	24	24	56	18	19	24
13 months or more	18	15	20	21	25	44	19	42	39
<b>South</b>									
3 months or less	7	8	10	34	45	45	49	32	82
4 to 6 months	2	3	6	9	15	28	17	20	13
7 to 9 months	6	8	9	11	7	24	14	13	8
10 to 12 months	10	12	11	13	9	41	11	10	9
13 months or more	12	13	18	17	11	33	21	15	10
<b>West</b>									
3 months or less	9	9	16	26	39	46	65	(A)	78
4 to 6 months	3	2	14	20	14	26	11	22	37
7 to 9 months	7	7	14	14	7	16	7	13	11
10 to 12 months	11	12	11	26	11	31	9	12	12
13 months or more	13	10	13	23	6	23	10	14	7

- Represents zero.

A Represents a relative standard error that is greater than or equal to 100 or could not be computed.

Z Less than 0.5 percent.

<sup>1</sup>Includes units built for rent (not shown separately).